

Bidding Calendar: September 2026

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
Northern Region						
1	Creation of 400/220 kV, 2x315 MVA (GIS) S/S at Siot, Jammu & Kashmir - Establishment of 7x105 MVA, 400/220 kV Siot (GIS) S/s with 1x80 MVAR (420 kV) bus reactor - LILO of 400 kV D/C Amargarh (Kunzer)- Samba line at 400/220 kV Siot (GIS) S/s	PFCCCL	28.04.2025	16.11.2026	18 Months from SPV transfer	
2	Transmission system for evacuation of power from Rajasthan REZ Ph-IV (Part-5: 6 GW) [Barmer Complex] Barmer-II: 6 GW (Solar) (LCC Configuration) - Establishment of 400/220 kV, 6x500 MVA S/s at suitable location near Barmer (Barmer-II Substation) along with 2x125 MVAR bus reactor - LILO of both circuits of 400 kV Fatehgarh-IV PS - Barmer-I PS D/C line at Barmer-II PS 400 kV Barmer-II PS - Barmer-I PS D/C line (Quad) - Establishment of 6000 MW, $\pm$ 800 kV Barmer-II (HVDC) [LCC] terminal station (4x1500 MW) at a suitable location near Barmer-II substation - Establishment of 6000 MW, $\pm$ 800 kV South Kalamb S/s (HVDC) [LCC] terminal station (4x1500 MW) at a suitable location near South of Kalamb $\pm$800 kV HVDC Bipole line (Hexa lapwing) between Barmer-II (HVDC) & South Kalamb (HVDC) (with parallel Dedicated Metallic Return) (capable to evacuate 6000 MW) [with 100% reverse power capability] - Augmentation of South Kalamb S/s by 4x1500 MVA, 765/400 kV ICTs (3 Nos 400 kV & 765 kV Section-II & 1 No. on 400 kV & 765 kV Section-I) along with 2x330 MVAR, 765 kV bus reactor & 2x125 MVAR, 420 kV bus reactor on Section-II. The Section-II will be established under a different network expansion scheme in WR (2x1500 MW HVDC Bipole-I to be terminated on 400 kV Section-I & 2x1500 MW HVDC Bipole-II to be terminated on 400 kV Section-II of South Kalamb S/s & 765 kV bus sectionalizer to be kept	RECPDCL	28.01.2026	23.09.2026	54 months from SPV transfer (Bipole-1: 48 months, Bipole-2: 54 months)	SPV Transferred

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	normally closed & 400 kV bus sectionalizer to be kept normally open) 2 Nos. of Syncon units at 400 kV level of Barmer-II PS (1 No. of SynCon unit comprises dynamic support of +300 MVar/-200 MVar (Minimum) & Short circuit contribution at PCC of 1200 MVA (Minimum))					
3	Transmission system for evacuation of power from Pumped Storage Projects in Sonbhadra District, Uttar Pradesh - Establishment of 3x1500 MVA 765/400 kV Robertsganj Pooling Station near Robertsganj area in Sonbhadra distt. (Uttar Pradesh) along with 2x240 MVar 765 kV & 2x125 MVar 400 kV bus reactors - LILO of both circuits of 765 kV Varanasi- Gaya 2xS/C line at Robertsganj PS along with 240MVar switchable line reactor at each ckt of Robertsganj PS end of 765 kV Robertsganj PS - Gaya 2xS/C line (after LILO) - Robertsganj PS – Prayagraj S/s 765 kV D/C line along with 330 MVar line reactor at each circuit of Robertsganj end of Robertsganj PS – Prayagraj S/s 765 kV D/C line	RECPDCL	21.04.2025		30 Months from SPV transfer	Bidding Concluded. SPV Transfer after receipt of FC-1 approval.
	Augmentation with 1x1500 MVA (4th), 765/400 kV ICT at Robertsganj Pooling Station				December 2030	
4	Transmission scheme for evacuation of power as part of Rajasthan REZ Ph-IV (Part-6: 6 GW) (Bikaner Complex) (Bikaner V: 6 GW)- Part A) - Establishment of 765/400 kV, 6x1500 MVA & 400/220 kV, 10x500 MVA Bikaner-V Pooling Station along with 2x240 MVar (765 kV) & 2x125 MVar (420 kV) Bus Reactors at a suitable location near Bikaner - STATCOM (2x ±300 MVar) along with MSC (4x125 MVar) & MSR (2x125 MVar) at Bikaner-V PS - LILO of one double ckt of 400 kV Bikaner II PS- Khetri (Twin HTLS) 2xD/c line at Bikaner-V PS along with 50 MVar	RECPDCL	14.08.2026	15.12.2026	36 Months from SPV transfer	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	switchable line reactor for each circuit at Bikaner-V PS end of 400 kV Bikaner-V-Khetri section - Establishment of 765/400 kV, 2x1500 MVA S/s at suitable location near Pallu (Distt. Hanumangarh) along with 2x240 MVar (765 kV) & 2x125 MVar (420 kV) Bus Reactors 765 kV Bikaner-V PS – Pallu 2xD/c line - LILO of both ckts of 765 kV Bikaner – Moga D/c line at Pallu S/s along with 240 MVar switchable line reactor for each circuit at Pallu S/s end of 765 kV Pallu-Moga D/c line 400 kV Pallu – Hanumangarh (RVPN) D/c (Quad) line					
5	Transmission scheme for evacuation of power as part of Rajasthan REZ Ph-IV (Part-6: 6 GW) (Bikaner Complex) (Bikaner V: 6 GW)- Part B) - Establishment of 765/400 kV, 3x1500 MVA S/s at suitable location near Panipat (Distt. Panipat) along with 2x240 MVar (765 kV) & 2x125 MVar (420kV) Bus Reactors 765 kV Pallu-Panipat 2xD/C line along with 240 MVar switchable line reactor for each circuit at each end - Establishment of 400/220 kV, 4x500 MVA S/s at suitable location near Mohali (Distt. Mohali district) along with 2x125 MVar (420 kV) Bus Reactors - LILO of one circuit of 400 kV Patiala-Panchkula D/C line at Mohali (Twin HTLS*) * With minimum capacity of 2100 MVA on each circuit at Nominal voltage 400 kV Panipat S/s – Mohali D/c (Quad Moose) line along with 80 MVar (420 kV) switchable line reactor for each circuit at Mohali end 400 kV Panipat S/s – Mandola D/C (Quad) line	RECPDCL	14.08.2026	15.12.2026	36 Months from SPV transfer	
6	Transmission scheme for evacuation of power as part of Rajasthan REZ Ph-IV (Part-6: 6 GW) (Bikaner Complex) (Bikaner V: 6 GW)- Part C) Establishment of 765 kV S/s at suitable location near Bulandshahr (Distt. Bulandshahr) along with 2x330 MVar (765kV) Bus Reactors	RECPDCL	14.08.2026	15.12.2026	36 Months from SPV transfer	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	765 kV Panipat- Bulandshahr 2xD/c line along with 240 MVAR switchable line reactor for each circuit at Bulandshahr end - LILO of 765kV Aligarh – Gr. Noida line at Bulandshahr S/s 765kV Bulandshahr - Noida sec-148 (UPPTCL) D/c line - Establishment of 765/400 kV, 2x1500 MVA Lucknow-II S/s at suitable location near Lucknow along with 2x330 MVAR (765kV) & 2x125 MVAR (420kV) Bus Reactors 765 kV Bulandshahr – Lucknow-II D/c line along with 330 MVAR switchable line reactor for each circuit at each end					
7	Transmission scheme for evacuation of power as part of Rajasthan REZ Ph-IV (Part-6: 6 GW) (Bikaner Complex) (Bikaner V: 6 GW)- Part D) 400 kV Lucknow-II – Gonda D/c (Quad Moose) line - Establishment of 765/400 kV, 2x1500 MVA S/s at suitable location near Asana Village (Chandauli District) along with 2x330 MVAR (765kV) & 2x125 MVAR (420kV) Bus Reactors 765 kV Lucknow-II-Asana D/c line along with 330 MVAR switchable line reactor for each circuit at each end - LILO of both ckts of 400kV Varanasi – Biharsharif D/c line (Quad) at Asana S/s along with 80 MVAR switchable line reactor for each circuit at Asana end of 400kV Asana- Biharsharif section - Asana – Nawada 765kV D/c line along with 330MVAR switchable line reactors in each circuit at Asana end	RECPDCL	14.08.2026	15.12.2026	36 Months from SPV transfer	
ER & NER						
1	ERES-47: Nawada – Durgapur – Jeerat (New) 765kV corridor - Establishment of new 765/400/220kV S/s at Nawada in Bihar - Establishment of new 765kV Switching station at Durgapur in West Bengal with provision for establishment of 765/400kV level in future - LILO of Gaya – Ballia 765kV S/c line Nawada S/s - Nawada – Durgapur (New) 765kV D/c line - Durgapur (New) – Jeerat (New) 765kV D/c line - Extension at Jeerat (New) 765/400kV S/s	RECPDCL	09.06.2026	09.10.2026	31.03.2029	
Western Region						

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
1.	Common Transmission System for evacuation of power from Lakadia (Phase-II: 7.5GW), Jam Khambhaliya (Phase-II: 5.5GW) and Jamnagar (Phase-I: 1GW) - Part-A - Augmentation of transformation capacity at South Olpad (GIS) S/s by 1x1500MVA, 765/400kV (3rd) ICT - Vadodara (GIS) – Halvad 765kV D/c line to be terminated into Lakadia – Halvad 765kV D/c line (near Halvad S/s) so as to form Lakadia – Vadodara (GIS) 765kV D/c line 765kV line bays at Vadodara (GIS) end for termination of Lakadia – Vadodara 765kV D/c line (formed as per details above at Sl. 2) 765kV, 240MVA Switchable line reactors on each circuit at Vadodara (GIS) end of Lakadia – Vadodara (GIS) 765kV D/c line (formed as per details above at Sl. 2) 765kV, 330MVA Switchable Mid-point reactors at the bypass point at Halvad Switching Station on Lakadia – Vadodara (GIS) 765kV D/c line (refer Note d)	PFCCCL	25.03.2026	05.10.2026	36 months from SPV transfer	
2.	Transmission system for Integration of Power from RE Projects in Jam Khambhaliya REZ in Gujarat - Phase II (5500MW) and Jamnagar Phase-I (1000 MW) - Establishment 4x1500 MVA, 765/400 kV and 10x500 MVA, 400/220 kV Substation near Kalyanpur (GIS) with 2x330 MVA, 765 kV bus reactor and 2x125 MVA, 420 kV bus reactor - Kalyanpur (GIS) – Jamnagar (GIS) 765 kV D/c line 2 Nos. 765 kV line bays at Jamnagar (GIS) S/s - Kalyanpur (GIS) – Saurashtra (Sompipaliya) (GETCO) (GIS) 765 kV D/C line 330MVA Switchable line reactors on each circuit at Saurashtra (Sompipaliya) (GETCO) (GIS) end of Kalyanpur (GIS) – Saurashtra (Sompipaliya) (GETCO) (GIS) 765 kV D/c line (with NGR bypass arrangement)	PFCCCL	12.03.2026	05.10.2026	31.03.2030	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	2 Nos. 765 kV line bays at Saurashtra (Sompipaliya) (GETCO) (GIS) S/s - Installation of Synchronous Condenser (+300/-200MVar) (Minimum) & Short circuit contribution at PCC of 1200 MVA (Minimum) at Kalyanpur (GIS)– 2 Nos. Value of Inertia (Minimum) shall be 3000 MW-s - Creation of 220 kV switchyard along with Installation of 3x500MVA, 400/220kV ICTs at Jamnagar (GIS) S/s 4 Nos. 220 kV line bays for RE interconnection at Jamnagar (GIS) S/s					
3.	Network Expansion Scheme in Western Region to cater to pumped storage potential near Satara (up to 4500 MW)- Part A Phase-I (Cumulative 1800 MW) - Creation of 765 kV level at Kolhapur (PG) GIS with installation of 2x1500 MVA, 765/400 kV ICTs at Kolhapur (PG) S/s along with upgradation of Kolhapur (PG) S/s to 765kV level - Installation of 765 kV, 2x330 MVAR bus reactors at Kolhapur GIS (PG) S/s. - Bay Works required for upgradation of Narendra (New) – Kolhapur (PG) 765 kV D/c line (presently charged at 400kV) to 765kV level. - Installation of 765kV, 330MVar switchable line reactors on each circuit at Kolhapur (PG) end of Narendra (New) Kolhapur (PG) 765kV D/c line - Establishment of 765/400 kV Satara Substation with 765/400 kV 3x1500 MVA ICTs, 765kV 2x330 MVAR bus reactors and 400 kV 1x125 MVAR bus reactor - LILO of Pune-III – Pune (East) 765kV D/c line at Satara Phase-II (Cumulative 4500 MW) - Creation of 400 kV Bus Section-II and augmentation of transformation capacity at 765/400 kV Satara S/s by 765/400 kV, 1x1500 MVA ICT (4th) along with 1x125 MVAR 400 kV bus reactor (on Bus Section-II)	PFCCCL	01.05.2026	06.10.2026	31.03.2029	
					31.12.2029	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	- Kolhapur (PG) – Satara 765kV D/c line 765 kV line bays for Kolhapur (PG) –Satara 765kV D/c line 765kV, 240 MVar switchable line reactors on each circuit at Satara end of Kolhapur (PG) – Satara 765kV D/c line					
4.	Common Transmission System for evacuation of power from Lakadia (Phase-II: 7.5GW), Jam Khambhaliya (Phase-II: 5.5GW) and Jamnagar (Phase-I: 1GW) - Part-C - Establishment of 765/400 kV, 2x1500MVA & 400/220kV, 3x500MVA Alephata S/s with 2x330 MVAR 765kV bus reactor and 2x125 MVAR 400kV bus reactor. [765kV & 400kV Bus sectionalisers to be kept normally closed. May be opened based on Grid conditions] - Alephata – Lonikand-I 400kV D/c line (Quad ACSR/AAAC/AL59 moose equivalent) 2 Nos. 400 kV Outdoor GIS line bays at Lonikand-I (MSETCL) S/s for Alephata – Lonikand-I 400 kV D/c line - LILO of Aurangabad – Pune (Shikrapur) (GIS) 765kV S/c line and Padghe (GIS) – Pune (Shikrapur) (GIS) 765kV S/c line at Alephata S/s (LILO route length ~ 20km.) - Nasik – Alephata 765kV D/c line 765 kV, 240 MVar Switchable Line Reactor on each circuit at Nasik end of Nasik – Alephata 765kV D/c line (with NGR bypass arrangement) 2 Nos. 765kV bays at Nasik for Nasik – Alephata 765kV D/c line	PFCCCL	12.03.2026	05.10.2026	36 months from SPV transfer	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
5.	Transmission system for Evacuation of Power from RE Projects in Solapur SEZ (Phase-II: 2 GW) and Network Expansion Scheme to Enable Drawl of Power from Solapur PS Part A: Network Expansion Scheme to enable drawl of power from Solapur PS - Installation of 2x500 MVA, 400/220 kV ICTs (5th & 6th) at Solapur PS (terminated on 400 kV bus section-1 and on segregated 220 kV bus section-2, other than the one where RE injection is planned (with space kept for ICT 7th on 400 kV bus section-1 and 220 kV bus section-2, to be planned, in future, as per requirement) 6 Nos. 220 kV line bays on 220 kV Bus Section-2 at Solapur PS for 220 kV downstream lines of MSETCL	PFCCCL	22.09.2026	28.12.2026	30 months from SPV transfer	
	Part B: Transmission system for Evacuation of Power from RE Projects in Solapur SEZ (Phase-II: 2 GW) - Creation of New 400 kV Bus Section-2 and 220 kV Bus Section-3 with 400 kV and 220 kV Bus Sectionalizers at Solapur PS, along with 3 Nos. 220 kV line bays on Bus Section-3 & 1 No. 400 kV bay on Bus Section-2 for RE Interconnection. 400/220 kV, 3x500 MVA ICT augmentation (8th, 9th & 10th) at Solapur PS on New 400 kV Bus Section-2 and 220 kV Bus Section-3 - Solapur PS (Bus Section-II) – Jejuri (MSETCL) 400 kV D/c line (Quad ACSR/ AAAC/ AL59 Moose equivalent) 400 kV line bays at Solapur PS (Bus Section-2) as well as Jejuri (MSETCL) for Solapur PS (Bus Section-II) – Jejuri (MSETCL) 400 kV D/c line 63 MVAr, 420 kV Switchable line reactors on each circuit at both ends of Solapur PS (Bus Section-2) – Jejuri (MSETCL) 400 kV D/C line (with NGR bypass arrangement) - Jejuri (M) – Pune-III 400 kV D/C line (Quad ACSR/ AAAC/ AL59 Moose equivalent)				36 months from SPV transfer	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	400 kV line bays at Pune-III as well as Jejuri (MSETCL) for Jejuri (M) – Pune-III 400 kV D/C line					
6.	Common Transmission System Augmentation for Evacuation of Power from 2x800 MW Gadawara TPS-II (NTPC) and an Additional 1500 MW RE power at Mandsaur PS - Part A - Augmentation of transformation capacity at Mandsaur PS by 2x1500 MVA, 765/400 kV ICTs (5th & 6th), terminated at 765 kV and 400 kV Bus Section-II. - Augmentation of transformation capacity at Mandsaur PS by 3x500 MVA, 400/220 kV ICTs (8th, 9th & 10th), terminated at 400 kV Bus Section II & 220 kV Bus Section-III. - Installation of ±400 MVar STATCOM at Mandsaur PS	PFCCCL	25.09.2026	28.12.2026	36 months from SPV transfer	
7.	Common Transmission System Augmentation for Evacuation of Power from 2x800 MW Gadawara TPS-II (NTPC) and an Additional 1500 MW RE power at Mandsaur PS - Part B - Establishment of 765 kV Gadawara-II Substation along with 2x330 MVar 765 kV bus reactors - Kurawar – Gadawara-II 765 kV D/C line, with LILO of one circuit at Bhopal (BDTCL) S/s 2 Nos. 765 kV line bays at Bhopal S/s for LILO of one circuit of Kurawar – Gadawara-II 765 kV D/C line 2 Nos. 765 kV line bays at Kurawar S/s for Kurawar – Gadawara-II 765 kV D/C line, with LILO of one circuit at Bhopal (BDTCL) S/s - Installation of 330 MVar Switchable Line Reactor at Gadawara-II end of Kurawar – Gadawara-II 765 kV line - Installation of 240 MVar Switchable Line Reactor at Bhopal (BDTCL) end of Bhopal (BDTCL) – Gadawara-II 765 kV line	PFCCCL	25.09.2026	28.12.2026	36 months from SPV transfer	
	Creation of 400 kV level at 765 kV Gadawara-II Substation and Implementation of 2x1500 MVA 765/400 kV ICTs along with 400 kV line bays				31.03.2031	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	2 Nos. 400 kV line bays at 765/400 kV Seoni (PG) S/s					
8.	Transmission system for Integration of Power from RE Projects in Lakadia REZ in Gujarat-Phase II (7500 MW) - Establishment of 765/400 kV, 6x1500 MVA & 10x500 MVA, 400/220 kV Lakadia-II (Near Chitrod) with 2x330 MVAR 765 kV bus reactor and 2x125 MVAR 400 kV bus reactor. - Installation of Synchronous Condenser (+300/-200 MVAR) (Minimum) & Short circuit contribution at PCC of 1200 MVA (Minimum) at Lakadia-II – 2 Nos. Value of Inertia (Minimum) shall be 3000 MW-s - LILO of Halvad – Kandla 765 kV D/c line at Lakadia-II - Lakadia-II – Ahmedabad 765 kV D/c line 2 Nos. 765 kV line bays at Ahmedabad S/s for Lakadia-II – Ahmedabad 765 kV D/c line 765 kV, 330 MVAR Switchable line reactors on each circuit at Ahmedabad end of Lakadia-II – Ahmedabad 765 kV D/c line - Lakadia-II – Vataman 765 kV D/c line 2 Nos. 765 kV line bays at Vataman S/s for Lakadia-II – Vataman 765 kV D/c line 765 kV, 240 MVAR Switchable line reactors on each circuit at both ends of Lakadia-II – Vataman 765 kV D/c line	RECPDCL	04.05.2026.	05.10.2026	36 months from SPV transfer	
9.	Common Transmission System for evacuation of power from Lakadia (Phase-II: 7.5 GW), Jam Khambhaliya (Phase-II: 5.5 GW), Jamnagar (Phase-I)- Part B - Establishment of 765/400 kV, 3x1500MVA & 400/220kV, 3x500MVA Nasik S/s (towards South of Nasik) with 2x330 MVAR 765kV bus reactor and 2x125 MVAR 400kV bus reactor. - South Olpad (GIS) – Nasik 765kV D/c line 2 Nos. 765 kV line bays at South Olpad (GIS) S/s (Sec-II) for South Olpad – Nasik 765kV D/c line 765kV, 240MVAR Switchable line reactors on each circuit at both ends of South Olpad – Nasik 765kV D/c line	RECPDCL	04.05.2026	05.10.2026	36 months from SPV transfer	

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	- Nasik – Pimpalgaon (MSETCL) 400kV D/c line (Quad ACSR/AAAC/AL59 moose equivalent) (Line to be routed from near Sinner TPP / Raymond i.e. from eastern side of Nasik). 2 Nos. 400 kV line bays (GIS) at Pimpalgaon (MSETCL) S/s for Nasik – Pimpalgaon (MSETCL) 400kV D/c line (Quad ACSR/AAAC/AL59 moose equivalent)					
Southern Region						
1.	Transmission System Strengthening at Karur PS for integration of RE generation capacity - Karur PS – Pugalur (HVDC) 400 kV (Quad) 2nd D/C line 400 kV line bays at Pugalur (HVDC) for Karur PS – Pugalur (HVDC) 400 kV (Quad) 2nd D/C line 400 kV line bays at Pugalur (existing) for Karur PS – Pugalur (existing) 400 kV (Quad) 2nd D/c line - Augmentation of 2x500 MVA, 400/230 kV ICTs (5th & 6th) at Karur PS - Karur PS – Pugalur (existing) 400 kV (Quad) 2nd D/c line 1 No. of 230 kV line bay at Karur PS for termination of dedicated transmission line of RE generation project	PFCCCL	22.09.2026	28.12.2026	30 Months from SPV transfer	
2.	Transmission system for proposed Green Hydrogen / Green Ammonia projects in Tuticorin area - Establishment of 3x1500 MVA, 765/400 kV Tuticorin (GH) S/s with 1x240 MVAr bus Reactor - Tuticorin PS – Tuticorin (GH) 765 kV D/c line - Upgradation of Tuticorin PS - Dharmapuri (Salem New) 765 kV D/C line (presently charged at 400 kV level) at its rated 765 kV voltage level with 1x330 MVAr switchable Line Reactor on both ends of each circuit - Transmission line for change of termination from 400 kV switchyard to 765 kV switchyard for Tuticorin PS – Dharmapuri (Salem New) 765 kV D/C line at Tuticorin PS and Dharmapuri (Salem New)	RECPDCL	17.10.2024		30 months from SPV transfer	Bidding- On Hold

Sr. No.	Transmission Scheme	Bidding Agency	RfP Issue Date	Expected SPV Transfer Date	SCOD	Remarks
	- Upgradation of Tuticorin PS to its rated voltage of 765 kV level alongwith 3x1500 MVA, 765/400 kV ICTs and 1x330 MVA, 765 kV bus reactors - Upgradation of Dharmapuri (Salem New) to its rated voltage of 765 kV level alongwith 3x1500 MVA, 765/400 kV ICTs and 1x330 MVA, 765 kV bus reactor 400 kV line reactors on Tuticorin PS - Dharmapuri (Salem New) 765 kV D/c line shall be utilized as bus reactors at respective 400 kV substations based on availability of bays. - Upgradation of Dharmapuri (Salem New) – Madhugiri 765 kV 2xS/C lines (presently charged at 400 kV) to its rated voltage at 765 kV with 1x330 MVA switchable Line Reactor on Dharmapuri (Salem New) end of each circuit - Transmission line for change of termination from 400 kV switchyard to 765 kV switchyard for Dharmapuri (Salem New) – Madhugiri 765 kV 2xS/c line at Dharmapuri (Salem New) & Madhugiri 400 kV line reactors on Dharmapuri (Salem New) – Madhugiri 765 kV 2xS/c lines shall be utilized as bus reactors at respective 400 kV substations based on availability of bays. ± 300 MVA STATCOM with 2x125 MVA MSC at Tuticorin 765/400 kV GH S/s with control switching arrangement for proposed 1x240 MVA bus reactor					